The current challenges and good practices of utilities

## "Progress of the Zinc Injection in Tsuruga NPP Unit 2"

Nobuaki, Nagata, The Japan Atomic Power Company, Japan



Zinc injection into the Tsuruga NPP unit 2 is implemented to assess Effect of water chemistry during zinc injection, Effect on dose reduction, and Evaluation of the fuel performance. At Tsuruga unit 2, 14<sup>th</sup> Cycle were implemented from 2005/10/ to injection zinc for 8 months, and the density of cooling material zinc was 5 ~ 7ppb.

Radioactive Co density (co-58 and Co-60) in the coolant during the zinc injecting period was increased by a factor of ten. Depleted zinc was used so that the density of Zn-65 was not observed.

By the effect of zinc injection, the dose rate of the primary equipment and pipes (Hot Leg, Cold Leg, and SG Water Room) was decreased by 20-30% compared with the rate of previous periodical inspection.

The surface of fuel covering pipe was not influenced even after zinc injection. In the thickness measurement of rotted film on fuel covering pipe, there was no difference between before and after zinc injection; therefore, it is concluded that zinc injection has no influence on corrosion of covering pipe.





